

**OFFICE OF THE REGISTRAR**  
**GURUCHARAN UNIVERSITY**  
**SILCHAR, CACHAR: ASSAM**  
**গুরুচরণ বিশ্ববিদ্যালয়**  
**শিলচর, কাছাড় : আসাম**

*A State University established by upgrading Gurucharan College under Assam Act No. LVII of 2023*

**Ref No. 131/Reg/E&E/2025/269**

**Date: 03-12-2025**

## **NOTICE INVITING QUOTATION**

Sealed quotations are invited from reputed Govt. Registered Contractor of APWD, State Govt., PSU etc. of appropriate class and category with sound financial capacity for the work of Repairing and Renovation of Printing Press to convert it into University canteen of G.C.University, Silchar. The construction should be done as per the approved design & drawing and proper quality has to be maintained. The contractor should submit relevant documents, all self-attested, as follows

1. Valid Govt. Contractor Registration Certificate,
2. Pan card, GST Registration Certificate with latest deposit payment challan copy (last 3 months)
3. Work order and Experience Certificate of Similar nature of Govt. work of value not less than 2.5 lakh (Single work)
4. Bank Solvency Certificate from nationalized/scheduled banks of value not less than 40% of estimated amount dated within one calendar year from date of submission of quotation
5. EPF Registration Certificate with proof of payment within two months from month of submission of quotation,
6. ESIC Registration Certificate with proof of payment within two months from month of submission of quotation,
7. Income tax return of last financial year
8. Non refundable Quotation fee of Rupees Five Hundred only in the form of demand draft/Cash receipt in favour of Principal, G.C. College, Silchar in **envelope – 1** marked as Technical bid and Rate of quotation in **envelope – 2** marked as price bid and both the envelopes should be inserted in another **envelope – 3** marked Quotation for Repairing and Renovation of Printing Press to convert it into University canteen of G.C.University, Silchar

Eligible Contractors who are proficient in similar nature of works are to quote their rate in Item Rate Basis and rate should be inclusive of all taxes and incidental charges. Bidder should write his full name and address on envelope no -3 as well as on Price Bid clearly. Successful Bidder has to complete the work within 15 (Fifteen) days from the date of

**OFFICE OF THE REGISTRAR**  
**GURUCHARAN UNIVERSITY**  
**SILCHAR, CACHAR: ASSAM**  
**গুরুচরণ বিশ্ববিদ্যালয়**  
**শিলচর, কাছাড় : আসাম**

*A State University established by upgrading Gurucharan College under Assam Act No. LVII of 2023*

**Ref No. 131/Reg/E&E/2025/269**

**Date: 03-12-2025**

issue of Work Order. Any shortfall in technical bid or Overwriting in price bid will lead to rejection of Quotaion.

Last date for submission of quotation is 10-12-2025 up to 1.00p.m. The contractor should submit price bid as per format given as annexure after visiting the site of construction in the tender box kept in Registrar Office of G.C. University, Silchar. Technical bids will be opened on 10-12-2025 at 1.30 p.m. in presence of bidders present.

**Ref. no.123/Reg/E&E/2025/269(A) dtd. 03-12-2025.**

**Copy to:**

1. PS to VC for information of the Hon'ble Vice Chancellor.
2. Website administrator for uploading in the website
3. University Notice Board.
4. Guard file.

  
Registrar

**Registrar**  
**Gurucharan University**  
**Silchar**

  
Registrar

**Registrar**  
**Gurucharan University**  
**Silchar**

Annexure						
PRICE BID						
SL.NO	ITEM NO	DESCRIPTION	UNIT	QTY	RATE (IN FIGURES and WORDS)	AMOUNT
1	11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. 11.41.2 Size of Tile 600x600 mm	Sqm	84.23		
		Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	37.89		12

		<p>Providing and fixing Modular Lay-In-Grid ceiling system which includes fixing of wall angle (of size 24x 24 x 3000 x 0.35 mm) screw fixed of the periphery of the walls/ partitions at the desired ceiling height with PVC dash fasteners (nylon sleeves) and steel screws at 300 mm centre to centre. GI pre-coated Main Tee runners (of size 24 x 38 x 3600 x 0.25 mm) then shall be suspended from the soffit/ purlins with 4 mm dia. GI wire hangers, soffit cleats (of size 27 x 35 x 25 x 1.6 mm) and Metal Anchor Fasteners (Rawl Plugs) (45 x 8 mm) at 1200 mm centre to centre. In case of Purlins, the hangers would be directly strapped around the purlins for suspension. Grid module size of 1200 x 600 mm shall then be achieved by insert fixing Cross Tee (of size 24 x 26 x 1200 x 0.25 mm), using the snap and bayonet fixing mechanism into the Main Tee runner and in direction perpendicular to it at 600 mm centre to centre. Finally, the grid module size of 600 x 600 mm shall be achieved by insert fixing Cross Tee (of size 24 x 26 x 600 x 0.25 mm), using the snap and bayonet fixing mechanism into the 1200 mm Cross Tee runner and in direction perpendicular to it at 600 mm centre to centre. Finally, 4/ 6mm pre-painted Everest Designer ceiling tile of size 595 x 595 mm (for grid module size of 600 x 600 mm) in Texture Cascade, shall be placed over the grid.</p>				
3	MARKET		Sqm	15.21		



4	13.9	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : 13.90.1 Old work (one or more coats)	Sqm	211.63		58
5	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: 13.47.1 New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	91.05		
6	13.8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	34.68		
7	13.58	Providing and applying two coats of fire retardant paint on cleaned wood / ply surface @ 3.5 sqm per litre per coat including preparation of base surface as per recommendations of manufacturer to make the surface fire retardant.	Sqm	7.92		
8	13.52	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete	Sqm	36.54		

9	18.7.6	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 18.7.6 50 mm nominal dia Pipes	Rm	6.5		
10		Repair of Windows including change of glasspanes, rollers, locks etc as per requirement Amount -Rs 5,000.00	L/S			
11		Internal Electrification including providing and fitting of 9 nos of Ceiling Fan, 12 nos of LED 20 watt Tubelight set, necessary wiring, connections and 4 nos of 12 watt LED Bulbs etc Amount -Rs 60,000.00	L/S			
NOTE:- Rate to be quoted in item rate basis for item nos 1 to 9 and rate to be quoted for item nos 10 and 11 as percentage below/above/at par on L/S amount indicated.						

Registrar

Registrar  
Guru Charan University  
Gillchar